

GPS #: 3857R2

Date Destroyed:

Date Revised: 9/9/2009

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 708/H-7

City / Location: Brea

Scale Factor: 1.00000587

Ellipsoid Red. Factor: 0.99999083

Combination Factor: 0.99999670

Convergence Angle: -00 55 12.26837

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 55 02.61641	117 55 27.59316	2281521.106	6053706.475	
2007.00	33 55 02.63264	117 55 27.61049	2281522.77	6053705.04	

References: PMB 56/28-30, RSB 149/21-36, CR 2001-0655, CR 2004-2092, CR 2009-0030

Description:

FD 2-1/2" BRASS DISK STAMPED "CALIF DEPT OF TRANSPORTATION" IN A WELL, DOWN 0.9' IN LIEU OF PUNCHED SPIKE AND OCS WASHER STAMPED "3857R1 02/01" FLUSH IN POUR ROCK ORIGINAL MONUMENT BEING SPIKE AND WASHER STAMPED "RCE 12588". MONUMENT WAS RESET PER CORNER RECORD # 2001-655. MONUMENT IS LOCATED AT THE CENTERLINE INTER OF IMPERIAL HWY. AND PALM ST.

