

GPS #: 3859R1

Date Destroyed:

Date Revised: 1/28/2004

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 738/E-1

City / Location: La Habra

Scale Factor: 1.00000586

Ellipsoid Red. Factor: 0.99999282

Combination Factor: 0.99999868

Convergence Angle: -00 55 50.64708

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 55 02.42083	117 56 37.43389	2281596.398	6047821.018	
2007.00	33 55 02.43703	117 56 37.45125	2281598.06	6047819.58	

References: RSB 149/21-36, CR 2003-1061

Description:

FD 2 1/2" BRASS DISK STAMPED "CALIF. DEPT. OF TRANSPORTATION", DOWN 0.6' IN WELL MON. MONUMENT WAS RESET PER CORNER RECORD #2003-1061 IN LIEU OF PUNCHED SPIKE AND WASHER DOWN 0.2' AT THE APPARENT CENTERLINE INTER OF IMPERIAL HWY. AND CYPRESS ST.

