

GPS #: 3862R1

Date Destroyed:

Date Revised: 1/28/2004

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 738/C-1

City / Location: La Habra

Scale Factor: 1.00000586

Ellipsoid Red. Factor: 0.99999519

Combination Factor: 1.00000105

Convergence Angle: -00 56 38.39814

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 55 02.44043	117 58 04.33021	2281718.186	6040498.742	
2007.00	33 55 02.45667	117 58 04.34764	2281719.85	6040497.30	

References: CALTRANS AORO42A 0022, RSB 149/21-36, CR 2003-1050

Description:

FD 2 1/2" BRASS DISK STAMPED "CALIF. DEPT. OF TRANSPORTATION", DOWN 0.6' IN WELL MON. MONUMENT WAS RESET PER CORNER RECORD #2003-1050 IN LIEU OF SPIKE AND WASHER DOWN 0.1' LOCATED, IN THE LEFT TURN LN. OF WESTBOUND IMPERIAL HWY. NEAR THE NOSE OF MEDIAN ISLAND, IN THE INTER OF IMPERIAL HWY. AND BEACH BLVD.

