

GPS #: 3864R1

Date Destroyed:

Date Revised: 11/11/2011

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 708/E-6

City / Location: La Habra

Scale Factor: 1.00000847

Ellipsoid Red. Factor: 0.99999167

Combination Factor: 1.00000014

Convergence Angle: -00 56 03.97965

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 55 54.66906	117 57 01.69620	2286910.633	6045862.688	
2007.00	33 55 54.68530	117 57 01.71358	2286912.30	6045861.25	

References: PMB 248/5-6, RSB 149/21-36, CR 2006-0821

Description:

FD SPIKE AND WASHER STAMPED "LS 5411", FLUSH PER CR 2006-0821 IN LIEU OF FD 2 1/2" O.C.S. BRASS DISK STAMPED "T3S R10W 1/4 55/58 12-77" DOWN 1.7' IN O.C.S. WELL MONUMENT WITH FOUR 2' PUNCHED SPIKE AND O.C.S. WASHER TANGENT OVER SWING TIES LOCATED AT THE CENTERLINE INTER OF WALNUT ST. AND LA HABRA BLVD.

