

GPS #: **3869R1**

Date Destroyed:

Date Revised: 3/26/2007

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 708/F-5

City / Location: La Habra

Scale Factor: 1.00000847

Ellipsoid Red. Factor: 0.99999039

Combination Factor: 0.99999887

Convergence Angle: -00 55 44.62233

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 55 54.69282	117 56 26.47018	2286864.767	6048830.553	
2007.00	33 55 54.70903	117 56 26.48749	2286866.43	6048829.12	

References: RSB 149/21-36, CR 2005-1014, CR 2006-0824

Description:

FD SPIKE AND WASHER STAMPED "LS 5411" IN LIEU OF PUNCHED SPIKE AND WASHER STAMPED "RCE 8244". MONUMENT WAS RESET PER CORNER RECORD # 2006-0824. MONUMENT IS LOCATED IN THE INTERSECTION OF LA HABRA BLVD. AND LEMON ST.

