

GPS #: **3873R1**

Date Destroyed:

Date Revised: 10/30/2014

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 709/A-6

City / Location: Brea

Scale Factor: 1.00000719

Ellipsoid Red. Factor: 0.99998856

Combination Factor: 0.99999575

Convergence Angle: -00 54 24.52317

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 55 29.18969	117 54 00.70747	2284090.268	6061070.443	
2007.00	33 55 29.20621	117 54 00.72455	2284091.96	6061069.03	

References: BREA FIELD BOOK C-6 PAGE 42, RSB 149/21-36, CR 2014-0303, CR 2014-1716

Description:

FD GEAR SPIKE AND WASHER STAMPED "LS 5411" FLUSH, PER CR 2014-1716 IN LIEU OF PUNCHED SPIKE AND BRASS WASHER STAMPED "RCE 20206" FLUSH AT THE CENTERLINE INTER OF LAMBERT RD. AND TAMARACK AVE.

