

GPS #: **3875R1**

Date Destroyed:

Date Revised: 9/24/2007

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 709/B-5

City / Location: Brea

Scale Factor: 1.00000851

Ellipsoid Red. Factor: 0.99998703

Combination Factor: 0.99999554

Convergence Angle: -00 54 12.13779

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 55 55.53999	117 53 38.16882	2286723.632	6063011.509	
2007.00	33 55 55.55657	117 53 38.18599	2286725.33	6063010.09	

References: BREA FIELD BOOK C-4 PAGE 25, RSB 149/21-36, CR 2007-0039, CR 2007-0488

Description:

FD SPIKE AND WASHER STAMPED "LS 5411", FLUSH. IN LIEU OF PUNCHED SPIKE AND WASHER STAMPED "RCE 20206", FLUSH. MONUMENT RESET PER CORNER RECORD 2007-0488. MONUMENT AT THE CENTERLINE INTERSECTION OF BREA BLVD. AND STATE COLLEGE BLVD. (EAST)/CENTRAL AVE. (WEST).

