

GPS #: **3879**

Date Destroyed:

Date Revised: 7/17/2010

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 708/J-5

City / Location: Brea

Scale Factor: 1.00000848

Ellipsoid Red. Factor: 0.99998664

Combination Factor: 0.99999512

Convergence Angle: -00 54 55.06317

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 55 54.75995	117 54 56.28352	2286749.249	6056428.993	
2007.00	33 55 54.77627	117 54 56.30070	2286750.92	6056427.57	

References: BREA FIELD BOOK C-6 PAGE 48, RSB 149/21-36, CR 2001-0651, CR 2010-0890

Description:

FD ONE SPIKE AND WASHER STAMPED "RCE 20206" AND 3 SPIKE AND OCS WASHERS, ALL BEING TANGENT-OVER 2.0' SWING TIES FOR THE ACTUAL POINT THAT FALLS ON SEWER MANHOLE LOCATED AT THE CENTERLINE INTER OF CENTRAL AVE. AND PUENTE ST.

