

GPS #: 3883R2

Date Destroyed:

Date Revised: 11/11/2011

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 708/E-5

City / Location: La Habra

Scale Factor: 1.00000980

Ellipsoid Red. Factor: 0.99998835

Combination Factor: 0.99999815

Convergence Angle: -00 56 04.07727

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 56 20.80588	117 57 01.87385	2289552.652	6045890.812	
2007.00	33 56 20.82217	117 57 01.89115	2289554.32	6045889.38	

References: CALTRANS AORO72C 0016, RSB 149/21-36, CR 2001-0652, CR 2010-2802

Description:

RE-ESTABLISHED AS 3883R2 FD SPIKE AND CALTRANS WASHER, FLUSH PER CR 2010-2802 IN LIEU OF FD PUNCHED SPIKE AND OCS WASHER STAMPED "3883R1 01-01" FLUSH, ORIGINAL MONUMENT BEING SPIKE. MONUMENT WAS RESET PER CORNER RECORD # 2001-652. MONUMENT IS LOCATED AT THE APPARENT CENTERLINE INTER OF WHITTIER BLVD. AND WALNUT ST.

