

GPS #: **3890R1**

Date Destroyed:

Date Revised: 1/28/2004

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 739/C-1

City / Location: Brea

Scale Factor: 1.00000490

Ellipsoid Red. Factor: 0.99998959

Combination Factor: 0.99999449

Convergence Angle: -00 54 00.20943

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 54 42.70442	117 53 16.46186	2279332.977	6064724.695	
2007.00	33 54 42.72106	117 53 16.47897	2279334.68	6064723.28	

References: RSB 149/21-36, CR 2003-1035

Description:

FD 2 1/2" BRASS DISK STAMPED "CALIF. DEPT. OF TRANSPORTATION", DOWN 0.6' IN WELL MON. MONUMENT WAS RESET PER CORNER RECORD #2003-1035 IN LIEU OF SQUARE HEAD BOLT AND CALIFORNIA DIVISION OF HWY.S WASHER FLUSH AT THE APPARENT CENTERLINE INTER OF IMPERIAL HWY. AND STATE COLLEGE BLVD.

