

GPS #: **3892R1**

Date Destroyed:

Date Revised: 4/28/2014

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 737/G-7

City / Location: La Mirada, Los Angeles Co.

Scale Factor: 0.99999836

Ellipsoid Red. Factor: 1.00000244

Combination Factor: 1.00000080

Convergence Angle: -00 58 04.45328

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 52 24.32738	118 00 40.93144	2265957.512	6027032.838	-50.909
2007.00	33 52 24.34313	118 00 40.94894	2265959.13	6027031.39	

References: RSB 149/21-36

Description:

FD GEAR SPIKE AND WASHER STAMPED "LS 8403",
FLUSH IN AC PER CR 2013-2521 IN LIEU OF FD 3 1/2"
BRASS CALIFORNIA DEPARTMENT OF
TRANSPORTATION DISK STAMPED "GPS 4-A 1989"
SET IN CONC. FLUSH WITH SURFACE AT THE
APPARENT CENTERLINE INTER OF KNOTT AVE. AND
ARTESIA BLVD.

NO
LOCATION
MAP