

GPS #: **3894R2**

Date Destroyed:

Date Revised: 1/11/2016

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 798/A-6

City / Location: Garden Grove

Scale Factor: 0.99998353

Ellipsoid Red. Factor: 1.00000289

Combination Factor: 0.99998642

Convergence Angle: -00 57 18.81975

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 46 25.74828	117 59 17.88856	2229598.270	6033429.649	
2007.00	33 46 25.76455	117 59 17.90558	2229599.94	6033428.24	

References: GARDEN GROVE TIE BOOK 2 PAGE 159, RSB 149/21-36, CR 2003-229, CR 2003-0931, CR 2001-1612, PM 2012-100

Description:

FD GEAR SPIKE AND WASHER STAMPED "LS 5921" FLUSH PER PM 2012-100 IN LIEU OF PK NAIL AND TAG STAMPED "LS 5411", FLUSH IN AC ,ORIGINAL MONUMENT BEING PUNCHED SPIKE AND WASHER WITH CITY OF GARDEN GROVE TAG FLUSH 1.28' E'LY FROM A BOLT. MONUMENT WAS RESET PER CR 2003-0931. SPIKE IS LOCATED AT THE CENTERLINE INTER OF GARDEN GROVE BLVD. AND FERN ST.

