

GPS #: **3897R1**

Date Destroyed:

Date Revised: 3/14/2001

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 796/G-6

City / Location: Rossmoor

Scale Factor: 0.99998397

Ellipsoid Red. Factor: 1.00000517

Combination Factor: 0.99998914

Convergence Angle: -01 00 34.87407

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 46 37.54889	118 05 14.66390	2231307.325	6003337.803	
2007.00	33 46 37.56510	118 05 14.68110	2231308.99	6003336.38	

References: MM 119/35-44, RSB 149/21-36, CR 2001-0523

Description:

FD C-NAIL AND SMALL BRASS TAG FLUSH IN A.C. IN LIEU OF ORIGINAL SPIKE DOWN 0.2' IN A.C. AT THE CENTERLINE INTER OF MARTHA ANN DR. AND WALKER LEE DR. MONUMENT WAS SET PER CORNER RECORD # 2001-523.

