

GPS #: **3899R1**

Date Destroyed:

Date Revised: 6/12/2000

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 797/D-4

City / Location: Garden Grove

Scale Factor: 0.99998585

Ellipsoid Red. Factor: 1.00000422

Combination Factor: 0.99999008

Convergence Angle: -00 59 03.29181

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 47 27.14725	118 02 28.00452	2236075.370	6017489.865	
2007.00	33 47 27.16341	118 02 28.02173	2236077.03	6017488.44	

References: RSB 149/21-36, CR 2000-0214

Description:

FD BRASS PIN AND OCS TAG IN POUR ROCK FLUSH ABOVE ORIGINAL MONUMENT IN LIEU OF GEAR SPIKE AND WASHER STAMPED "JOHNSON - FRANK GPS STA LS 4215" FLUSH IN A.C. LOCATED 57'+/- S'LY FROM THE INTER OF BARTLETT ST. AND SANTA BARBARA AVE., 9.6'+/- E'LY FROM THE W'LY CURB ALONG BARTLETT ST.

