

GPS #: 3998

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 708/B-6

City / Location: La Habra

Scale Factor: 1.00000785

Ellipsoid Red. Factor: 0.99999166

Combination Factor: 0.99999951

Convergence Angle: -00 56 49.15887

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 55 42.35185	117 58 23.91233	2285779.421	6038915.340	174.327
2007.00	33 55 42.36813	117 58 23.92976	2285781.09	6038913.90	

References: NGS PID# DX4825, RSB 149/21-36

Description:

FD 3 1/2" BRONZE NATIONAL GEODETIC SURVEY CONTROL DISK STAMPED "DEXFORD 1973" IN TOP OF A 12" DIA. CONC. POST DOWN 0.3' IN GROUND. TO REACH THE STATION FROM THE INTER OF BEACH BLVD. AND LA HABRA BLVD., PROCEED WEST ON LA HABRA BLVD. 0.3 MILE TO DEXFORD DR. TURN LEFT AND GO SOUTH ALONG DEXFORD DR. 0.2 MILE TO THE END OF THE DR. AT TERRAZA PARK. STATION IS LOCATED, IN THE W'LY PORTION OF THE PARK 23.7' NORTH OF A 4' HIGH CHAIN LINK FENCE, 52' SOUTH SE OF THE SE CORNER OF A BLOCK WALL, 11.3' SW OF A LIGHT POLE, 29.5' EAST NE OF A 4" TREE.

