

## HORIZONTAL CONTROL DATA SHEET CCS83, ZONE VI



**GPS #:** 4124

**Date Destroyed:** 

**Date Revised:** 

**Benchmark Designation:** 

OCS Index Map: 5LA
Page/Grid: 829/H-3
City / Location: Santa Ana


Scale Factor: 0.99997978

Ellipsoid Red. Factor: 0.99999353

Combination Factor: 0.99997330

Convergence Angle: -00 52 38.93144

Factors and Convergance Angle based on



 Epoch Adjustment
 Latitude
 Longitude
 Northing (ft)
 Easting (ft)
 Ellipsoid Height (ft)

 1991.35
 33 44 41.29716
 117 50 48.55396
 2218353.713
 6076258.084
 135.295

 2007.00
 33 44 41.31353
 117 50 48.57042
 2218355.39
 6076256.72

References: NGS PID# DX4450, RSB 150/10-23

## **Description:**

FD 3 3/4" O.C.S. ALUMINUM DISK STAMPED "ROYAL 1973" CEMENTED TO THE TOP OF A 9" SQUARE, 2" HIGH CONC. BLOCK THAT IS CEMENTED TO THE TOP OF THE ROOF OF THE DAYS INN HOTEL AT 1600 EAST 1st ST.

