

GPS #: **4156R1**

Date Destroyed:

Date Revised: 6/6/1996

Benchmark Designation:

OCS Index Map: 4LA

Page/Grid: 799/A-7

City / Location: Garden Grove

Scale Factor: 0.99998264

Ellipsoid Red. Factor: 1.00000074

Combination Factor: 0.99998338

Convergence Angle: -00 54 47.15807

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 46 01.61171	117 54 41.89795	2226778.952	6056685.498	
2007.00	33 46 01.62798	117 54 41.91484	2226780.62	6056684.10	

References: PMB 237/12-13, RSB 149/37-43, CITY OF GARDEN GROVE TIE BOOK 2 PAGE 176A

Description:

FD 2 1/2" CITY OF GARDEN GROVE BRASS DISK
DOWN 12" IN WELL MONUMENT. STATION IS
LOCATED AT CENTERLINE INTER OF TRASK AVE.
AND CLINTON ST.

