

**GPS #:** 4169R2

Date Destroyed:

Date Revised: 4/6/2005

Benchmark Designation:

OCS Index Map: 4LA

Page/Grid: 828/H-1

City / Location: Garden Grove

Scale Factor: 0.99998167

Ellipsoid Red. Factor: 1.00000148

Combination Factor: 0.99998315

Convergence Angle: -00 55 21.39160

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 45 34.96956	117 55 44.19539	2224170.493	6051383.550	
2007.00	33 45 34.98594	117 55 44.21217	2224172.17	6051382.16	

References: RSB 149/37-43, CR 2004-0726, 2004-1745

## Description:

FD CSA MONUMENT WITH BRASS DISK IN LIEU OF PUNCHED SPIKE WITH BRASS WASHER IN LIEU OF PUNCHED SPIKE WITH BRASS WASHER, STAMPED "CSA" AND FOUR 2' PUNCHED CUT SPIKE AND WASHER TANGENT OVER TIES. MONUMENT WAS RESET PER CORNER RECORD # 2004-1745. STATION IS LOCATED AT THE INTERSECTION OF NEWHOPE ST. AND WESTMINSTER AVE.

