

GPS #: **4181**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 4LA

Page/Grid: 828/G-6

City / Location: Fountain Valley

Scale Factor: 0.99997720

Ellipsoid Red. Factor: 1.00000342

Combination Factor: 0.99998062

Convergence Angle: -00 55 37.70548

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 43 25.10859	117 56 13.88303	2211086.067	6048664.979	-71.401
2007.00	33 43 25.12483	117 56 13.89990	2211087.73	6048663.58	

References: RSB 119/44, RSB 149/37-43

Description:

FD PUNCHED 2" BRASS CAP, DOWN 0.9' IN TRIANGULAR WELL MONUMENT. STATION IS LOCATED AT CENTERLINE INTER OF EUCLID ST. AND HEIL AVE.

