

GPS #: 4185R1

Date Destroyed:

Date Revised: 3/14/2001

Benchmark Designation:

OCS Index Map: 4LA

Page/Grid: 828/G-2

City / Location: Santa Ana

Scale Factor: 0.99998101

Ellipsoid Red. Factor: 1.00000217

Combination Factor: 0.99998319

Convergence Angle: -00 55 38.47569

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 45 16.52752	117 56 15.28465	2222348.944	6048728.887	
2007.00	33 45 16.54389	117 56 15.30139	2222350.62	6048727.50	

References: MM 252/11-13, RSB 149/37-43 CR 1999-0047

Description:

FD NAIL AND "CITY OF SANTA ANA" TAG, FLUSH ON SURFACE IN LIEU OF PUNCHED SPIKE NO WASHER, DOWN 0.15'. MONUMENT WAS SET PER CORNER RECORD # 99-47. STATION IS LOCATED AT CENTERLINE INTER OF EUCLID ST. AND OAKFIELD AVE.

