

**GPS #:** 4196

Date Destroyed:

Date Revised: 10/16/2006

Benchmark Designation:

OCS Index Map: 4LA

Page/Grid: 858/F-2

City / Location: Fountain Valley

Scale Factor: 0.99997469

Ellipsoid Red. Factor: 1.00000426

Combination Factor: 0.99997895

Convergence Angle: -00 55 54.35991

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 42 06.47925	117 56 44.19038	2203180.699	6045976.189	-88.953
2007.00	33 42 06.49556	117 56 44.20739	2203182.37	6045974.78	

References: MM 274/32-33, RSB 149/37-43, CR2005-1209, CR 2006-0410

**Description:**

FD PUNCHED 2 1/2" STATE OF CALIFORNIA DIVISION OF HWY.S BRASS DISK, DOWN 0.8' IN WELL MONUMENT. STATION IS LOCATED AT CENTERLINE INTER OF WARD ST. AND TALBERT AVE.

