

**GPS #:** 4198

**Date Destroyed:** 7/25/2000  
**Date Revised:** 3/11/2004  
**Benchmark Designation:**  
**OCS Index Map:** 4LA  
**Page/Grid:** 828/E-7  
**City / Location:** Fountain Valley

**Scale Factor:** 0.99997634  
**Ellipsoid Red. Factor:** 1.00000388  
**Combination Factor:** 0.99998022  
**Convergence Angle:** -00 56 11.92475

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 42 58.55808	117 57 16.15450	2208488.208	6043362.109	-81.165
2007.00	33 42 58.57431	117 57 16.17151	2208489.87	6043360.70	

**References:** MM 424/49-50, RSB 149/37-43

**Description:**

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD METAL SHANK DOWN 1.5' IN O.C.S. WELL MONUMENT WITH (3) 2' PUNCHED SPIKE SURFACE TIES. STATION IS LOCATED AT CENTERLINE INTER OF BROOKHURST ST. AND WARNER AVE.

NO  
LOCATION  
MAP