

GPS #: 4206R1

Date Destroyed:

Date Revised: 5/3/2004

Benchmark Designation:

OCS Index Map: 4LA

Page/Grid: 828/D-1

City / Location: Garden Grove

Scale Factor: 0.99998228

Ellipsoid Red. Factor: 1.00000237

Combination Factor: 0.99998466

Convergence Angle: -00 56 22.46946

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 45 51.79043	117 57 35.34356	2226023.051	6042028.546	
2007.00	33 45 51.80662	117 57 35.36040	2226024.71	6042027.15	

References: MM 132/18-19, RSB 149/37-43, CR 2001-0296

Description:

FD PK NAIL AND CALTRANS WASHER FLUSH IN AC IN LIEU OF SPIKE (NO WASHER) AND TIN. MONUMENT HAS BEEN RESET PER CORNER RECORD # 2001-296. STATION IS LOCATED AT CENTERLINE INTER OF CORK ST. AND TEAL AVE.

