

GPS #: 4216

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 4LA

Page/Grid: 828/C-4

City / Location: Westminster

Scale Factor: 0.99997888

Ellipsoid Red. Factor: 1.00000369

Combination Factor: 0.99998257

Convergence Angle: -00 56 46.85552

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 44 15.24982	117 58 19.72076	2216327.496	6038121.359	-77.146
2007.00	33 44 15.26604	117 58 19.73776	2216329.16	6038119.95	

References: A/5-11&12 412, RSB 149/37-43

Description:

FD PUNCHED 2" O.C.S. ALUMINUM CAP, STAMPED "8-76", DOWN 1.7' IN WELL MONUMENT. STATION IS LOCATED AT CENTERLINE INTER OF MAGNOLIA ST. AND McFADDEN AVE.

