

GPS #: **4224**

Date Destroyed: **7/26/2000**

Date Revised:

Benchmark Designation:

OCS Index Map: **4LA**

Page/Grid: **828/B-3**

City / Location: **Westminster**

Scale Factor: **0.99997978**

Ellipsoid Red. Factor: **1.00000362**

Combination Factor: **0.99998340**

Convergence Angle: **-00 56 58.41968**

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 44 41.23959	117 58 40.76496	2218983.636	6036387.947	-75.676
2007.00	33 44 41.25592	117 58 40.78183	2218985.31	6036386.55	

References: **A/5-11&12 589, RSB 149/37-43**

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD STEEL SHANK, DOWN 0.6'. DOES NOT FIT DESTROYED - FD 3.0' PUNCHED SPIKE AND O.C.S. WASHER TIES. STATION IS LOCATED ALONG THE CENTERLINE OF BOLSA AVE., 0.08' WEST FROM ITS CENTERLINE INTER WITH PURDY ST.