

**GPS #:** 4233R1

**Date Destroyed:** 6/7/2001

**Date Revised:**

**Benchmark Designation:**

**OCS Index Map:** 4LA

**Page/Grid:** 797/J-6

**City / Location:** Garden Grove

**Scale Factor:** 0.99998353

**Ellipsoid Red. Factor:** 1.00000304

**Combination Factor:** 0.99998656

**Convergence Angle:** -00 57 27.44499

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 46 25.64476	117 59 33.58460	2229609.927	6032104.675	
2007.00	33 46 25.66099	117 59 33.60155	2229611.59	6032103.27	

**References:** CR 0717, RSB 149/21-36

**Description:**

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD SPIKE AND WASHER STAMPED "CALTRANS RCE 26087" IN LIEU OF PUNCHED 2" "CALIFORNIA DIVISION OF HIGHWAYS" BRASS CAP IN WELL MONUMENT. MONUMENT HAS BEEN RESET PER CORNER RECORD # 717. STATION IS LOCATED ALONG THE CENTERLINE OF GARDEN GROVE BLVD. AND THE SURVEY CENTERLINE OF BEACH BLVD.