

GPS #: 4236

Date Destroyed:

Date Revised: 9/20/2007

Benchmark Designation:

OCS Index Map: **4LA**

Page/Grid: 827/J-2

City / Location: Westminster

Scale Factor: 0.99998067

Ellipsoid Red. Factor: 1.00000386

Combination Factor: 0.99998453

Convergence Angle: -00 57 38.75530

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 45 06.83129	117 59 54.16684	2221673.460	6030233.878	-80.666
2007.00	33 45 06.84756	117 59 54.18372	2221675.13	6030232.48	

References: RSB 149/37-43, CR 2004-0061, CR 2007-0594, CR 2007-1163

Description:

FD PUNCHED 2 1/2" BRASS DISK (NO STAMPING),
DOWN 1.0' IN O.C.S. WELL MONUMENT. STATION IS
LOCATED SW'LY FROM THE APPARENT
CENTERLINE INTERSECTION OF HAZARD AVE. AND
HOOVER ST.

