

GPS #: 4239

Date Destroyed:

Date Revised: 7/17/2010

Benchmark Designation:

OCS Index Map: 4LA

Page/Grid: 827/H-1

City / Location: Westminster

Scale Factor: 0.99998160

Ellipsoid Red. Factor: 1.00000381

Combination Factor: 0.99998540

Convergence Angle: -00 57 56.09495

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 45 32.81487	118 00 25.72113	2224344.357	6027614.178	-79.577
2007.00	33 45 32.83108	118 00 25.73815	2224346.02	6027612.77	

References: MM 488/41-42, RSB 149/37-43, CR 2009-3216, CR 2010-0156

Description:

FD 3/4" BRASS WASHER AND NAIL, DOWN 1.9' IN O.C.S. WELL MONUMENT. STATION IS LOCATED AT CENTERLINE INTER OF WESTMINSTER BLVD. AND GOLDEN WEST ST.

