

GPS #: **4240R1**

Date Destroyed:

Date Revised: 4/5/2005

Benchmark Designation:

OCS Index Map: 4LA

Page/Grid: 797/H-7

City / Location: Westminster

Scale Factor: 0.99998254

Ellipsoid Red. Factor: 1.00000354

Combination Factor: 0.99998609

Convergence Angle: -00 57 53.36411

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 45 59.00774	118 00 20.75164	2226984.558	6028078.275	
2007.00	33 45 59.02395	118 00 20.76860	2226986.22	6028076.87	

References: MM 455/28-30, RSB 149/37-43, CR 2004-0992, CR 2004-1251

Description:

FD PK NAIL AND WASHER STAMPED "LS 6970" IN LIEU OF PUNCHED SPIKE AND WASHER, STAMPED "LS 4279". MONUMENT WAS RESET PER CORNER RECORD # 2004-1251. STATION IS LOCATED AT CENTERLINE INTER OF SHOOTING STAR CIRCLE AND TRASK AVE.

