

GPS #: 4249

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 4LA

Page/Grid: 797/F-7

City / Location: Westminster

Scale Factor: 0.99998338

Ellipsoid Red. Factor: 1.00000413

Combination Factor: 0.99998750

Convergence Angle: -00 58 26.16157

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 46 21.67522	118 01 20.43573	2229360.764	6023079.263	-86.197
2007.00	33 46 21.69147	118 01 20.45267	2229362.43	6023077.86	

References: CALTRANS AORO22B 22, RSB 149/37-43

Description:

FD PUNCHED 2 1/2" CALIFORNIA DIVISION OF HWY.S BRASS DISK, DOWN 1.1' IN WELL MONUMENT. STATION IS LOCATED AT THE END OF CURVE ALONG CENTERLINE OF SPRINGDALE ST., 700'+/- S'LY FROM ITS APPARENT CENTERLINE INTER WITH GARDEN GROVE BLVD.

