

GPS #: **4326R1**

Date Destroyed:

Date Revised: 6/10/2008

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 1023/B-1

City / Location: San Clemente

Scale Factor: 0.99995486

Ellipsoid Red. Factor: 0.99999922

Combination Factor: 0.99995408

Convergence Angle: -00 44 25.08140

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 24 09.31783	117 35 49.85653	2092767.123	6150530.678	
2007.00	33 24 09.33474	117 35 49.87186	2092768.85	6150529.40	

References: RSB 151/1-11, CR 2008-0371, CR 2008-0543

Description:

FD SPIKE AND WASHER STAMPED "LS 5411" FLUSH PER CR 2008-0543, IN LIEU OF: FD PUNCHED SPIKE AND STATE OF CALIF. DEPARTMENT OF TRANSPORTATION TAG FLUSH IN A.C. LOCATED AT APPARENT CENTERLINE OF AVENIDA DEL PRESIDENTE, 50'+/- E'LY OF SE CORNER OF THE CHAIN LINK BOUNDARY FENCE OF SAN CLEMENTE STATE BEACH PARK. MONUMENT IS 30'+/- SE'LY OF PEDESTRIAN BRIDGE OVER THE AVENIDA AT INTER OF UNNAMED PRIVATE DR. TO THE SW.

