

GPS #: 4329R1

Date Destroyed:

Date Revised: 2/23/2006

Benchmark Designation:

OCS Index Map: **6LB**

Page/Grid: 992/J-4

City / Location: San Clemente

Scale Factor: 0.99995540

Ellipsoid Red. Factor: 0.99999585

Combination Factor: 0.99995125

Convergence Angle: -00 44 55.44741

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 25 29.76172	117 36 45.11591	2100958.098	6145952.698	
2007.00	33 25 29.77868	117 36 45.13126	2100959.83	6145951.42	

References: RSB 151/1-11, CR 1998-0195

Description:

FD GEAR SPIKE AND WASHER STAMPED "LS 5939"
FLUSH, IN LIEU OF PUNCHED SPIKE AND WASHER
STAMPED "RCE 10035" FLUSH IN A.C. LOCATED AT
THE APPARENT CENTERLINE INTERSECTION OF
AVENIDA ROSA AND AVENIDA MONTEREY.
MONUMENT WAS RESET 04/22/98 PER CR # 98-195.

