

GPS #: **4330R1**

Date Destroyed:

Date Revised: 8/1/2006

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 992/H-5

City / Location: San Clemente

Scale Factor: 0.99995533

Ellipsoid Red. Factor: 1.00000011

Combination Factor: 0.99995544

Convergence Angle: -00 45 12.07710

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 25 21.10099	117 37 15.37828	2100116.416	6143376.568	
2007.00	33 25 21.11797	117 37 15.39362	2100118.15	6143375.29	

References: MM 351/49-50, RSB 151/1-11, CR 2003-1665B

Description:

FD GEAR SPIKE AND WASHER STAMPED "LS 6970" FLUSH, IN LIEU OF FD 2" I.P. WITH PUNCHED SPIKE, DOWN 0.2'. STATION IS LOCATED AT RADIUS POINT OF CORTO LN. CUL-DE-SAC. MONUMENT WAS RESET PER CORNER RECORD # 2003-1665B.

