

GPS #: 4335R1

Date Destroyed:

Date Revised: 3/5/1999

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 992/F-1

City / Location: San Clemente

Scale Factor: 0.99995613

Ellipsoid Red. Factor: 0.99999885

Combination Factor: 0.99995498

Convergence Angle: -00 45 53.82663

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 26 54.54314	117 38 31.35313	2109645.515	6137063.910	
2007.00	33 26 54.56012	117 38 31.36875	2109647.25	6137062.61	

References: CR 0918, RSB 151/1-11

Description:

FD GEAR SPIKE WITH 1 1/4" ALUMINUM WASHER STAMPED "LS 4653" FLUSH ON A.C. IN LIEU OF PUNCHED SPIKE AND OCS BRASS TAG STAMPED "RESET" GPS 4335 1-95" FLUSH IN A.C. STATION IS LOCATED AT APPARENT CENTERLINE INTER OF VIA SAN GORGONIO AND CALLE VISTA TORITO.

