

GPS #: **4344R1**

Date Destroyed:

Date Revised: 6/6/2001

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 993/A-5

City / Location: San Clemente

Scale Factor: 0.99995529

Ellipsoid Red. Factor: 0.99999163

Combination Factor: 0.99994692

Convergence Angle: -00 44 42.72911

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 25 15.04515	117 36 21.97142	2099445.184	6147894.761	
2007.00	33 25 15.06205	117 36 21.98670	2099446.91	6147893.49	

References: RSB 151/1-11, CR 2001-1054

Description:

FD PUNCHED SPIKE AND 1 1/4" OCS BRASS WASHER STAMPED "4344R1 5-01" FLUSH, IN LIEU OF PUNCHED SPIKE AND STATE OF CALIFORNIA DIVISION OF HWY.S TAG. MONUMENT WAS RESET PER CORNER RECORD # 2001-1054. MONUMENT IS LOCATED AT THE VISUAL CENTERLINE BEGINNING OF CURVE ALONG CALLE ALCAZAR, 110'+/- NW'LY FROM ITS INTER WITH AVENIDA CORDOBA.

