

GPS #: 4362

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 972/D-5

City / Location: San Juan Capistrano

Scale Factor: 0.99995695

Ellipsoid Red. Factor: 0.99999028

Combination Factor: 0.99994722

Convergence Angle: -00 46 23.91173

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 28 11.62732	117 39 26.10134	2117498.360	6132530.629	203.182
2007.00	33 28 11.64414	117 39 26.11731	2117500.08	6132529.30	

References: RSB 151/1-11

Description:

FD GEAR SPIKE AND BRASS WASHER, STAMPED "LS 4400", FLUSH. STATION IS LOCATED AT APPARENT CENTERLINE INTER OF CAMINO LAS RAMBLAS AND AVENIDA PESCADOR.

