

**GPS #:** 4363R1

Date Destroyed:

Date Revised: 6/6/2001

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 972/E-5

City / Location: San Juan Capistrano

Scale Factor: 0.99995699

Ellipsoid Red. Factor: 0.99998164

Combination Factor: 0.99993864

Convergence Angle: -00 46 05.02521

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 28 15.51414	117 38 51.73207	2117852.027	6135447.050	
2007.00	33 28 15.53100	117 38 51.74793	2117853.75	6135445.73	

References: RSB 151/1-11, CR 2001-1055

**Description:**

FD PUNCHED SPIKE AND 1 1/4" OCS BRASS WASHER STAMPED "4363R1 5-01", IN LIEU OF GEAR SPIKE AND BRASS WASHER, STAMPED "LS 4400". MONUMENT WAS RESET PER CORNER RECORD # 2001-1055. STATION IS LOCATED 30'+/- E'LY FROM THE APPARENT CENTERLINE INTER OF CAMINO LAS RAMBLAS AND KINKERRY LN.

