

GPS #: **4373**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 972/D-2

City / Location: San Juan Capistrano

Scale Factor: 0.99995809

Ellipsoid Red. Factor: 1.00000119

Combination Factor: 0.99995928

Convergence Angle: -00 46 19.74881

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 29 42.63452	117 39 18.52577	2126687.472	6133296.260	-24.928
2007.00	33 29 42.65144	117 39 18.54186	2126689.20	6133294.92	

References: RSB 100/46, RSB 151/1-11

Description:

FD PUNCHED HEX BAR, DOWN 1.0' IN O.C.S. WELL MONUMENT. STATION IS LOCATED, IN THE MOST N'LY, EASTBOUND TRAFFIC LN. ALONG SAN JUAN CREEK RD., 0.5 MILE +/- NE OF THE INTER WITH THE SAN DIEGO FREEWAY <5>.

