

GPS #: 4389R1

Date Destroyed:
Date Revised: 6/7/2012
Benchmark Designation:
OCS Index Map: 6LB
Page/Grid: 952/C-6
City / Location: San Juan Capistrano

Scale Factor: 0.99995938
Ellipsoid Red. Factor: 0.99999472
Combination Factor: 0.99995410
Convergence Angle: -00 46 37.56907

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 31 11.06429	117 39 50.95470	2135661.910	6130671.479	
2007.00	33 31 11.08144	117 39 50.97054	2135663.66	6130670.16	

References: RSB 151/1-11, CR 2001-1057, CR 2011-3483

Description:

FD PUNCHED SPIKE AND 1 1/4" OCS BRASS WASHER STAMPED "4389R1 5-01", IN LIEU OF PUNCHED ROUND HEAD SPIKE AND ALUMINUM WASHER WITH LARGE TIN, STAMPED "RCE _9890", FLUSH. MONUMENT WAS RESET PER CORNER RECORD # 2001-1057. STATION IS LOCATED AT THE VISUAL CENTERLINE ALONG RANCHO VIEJO RD., 55' +/- S'LY FROM ITS INTER WITH MALASPINA RD.

