

GPS #: 4399

Date Destroyed: 3/24/2003

Date Revised:

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 993/B-6

City / Location: San Clemente

Scale Factor: 0.99995517

Ellipsoid Red. Factor: 0.99999242

Combination Factor: 0.99994760

Convergence Angle: -00 44 27.68282

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 24 58.58909	117 35 54.59053	2097751.943	6150193.792	158.330
2007.00	33 24 58.60602	117 35 54.60580	2097753.67	6150192.52	

References: MM 439/48-50, RSB 151/1-11

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD SPIKE AND ALUMINUM WASHER, STAMPED "RCE 10609", FLUSH. STATION IS LOCATED AT CENTERLINE POINT OF REVERSE CURVE ALONG AVENIDA SAN GABRIEL, 175'+/- N'LY OF AVENIDA SAN PABLO.

NO
LOCATION
MAP