

GPS #: 4400R2

Date Destroyed:

Date Revised: 7/27/2006

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 993/A-4

City / Location: San Clemente

Scale Factor: 0.99995555

Ellipsoid Red. Factor: 0.99998609

Combination Factor: 0.99994165

Convergence Angle: -00 44 45.62283

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 25 49.47439	117 36 27.23737	2102930.610	6147493.781	
2007.00	33 25 49.49132	117 36 27.25274	2102932.34	6147492.50	

References: RSB 151/1-11, CR 2001-1058, CR 2006-1076

Description:

FD. SPIKE AND WASHER STAMPED "LS 5411", IN LIEU OF, FD PUNCHED SPIKE AND 1 1/4" OCS BRASS WASHER STAMPED "4400R1 5-01", IN LIEU OF CONC. NAIL AND LARGE TIN. MONUMENT WAS RESET PER CORNER RECORD # 2001-1058. STATION IS LOCATED AT THE VISUAL RADIUS POINT OF CUL-DE-SAC AT SE'LY END OF CALLE BALBOA.

