

**GPS #:** **4403R1**

Date Destroyed:

Date Revised: 9/13/2007

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 993/B-4

City / Location: San Clemente

Scale Factor: 0.99995544

Ellipsoid Red. Factor: 0.99997177

Combination Factor: 0.99992721

Convergence Angle: -00 44 31.78788

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 25 34.89920	117 36 02.06081	2101429.849	6149608.186	
2007.00	33 25 34.91607	117 36 02.07614	2101431.57	6149606.91	

References: RSB 151/1-11, CR 2004-0913, CR 2007-0281

**Description:**

FD SPIKE AND WASHER, STAMPED "L.S. 5411". IN LIEU OF PUNCHED SPIKE AND WASHER, (ILLEGIBLE) FLUSH. MONUMENT WAS RESET PER CORNER RECORD 2007-0281. STATION IS LOCATED IN THE CENTER OF STREET, AT POINT OF REVERSE CURVE OF AVENIDA SALVADOR, 0.25+/- MILE N'LY FROM ITS INTERSECTION WITH AVENIDA SAN JUAN.

