

GPS #: 4404

Date Destroyed:

Date Revised: 4/6/2000

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 952/G-6

City / Location: San Juan Capistrano

Scale Factor: 0.99995902

Ellipsoid Red. Factor: 0.99999737

Combination Factor: 0.99995639

Convergence Angle: -00 45 20.95424

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 30 47.50668	117 37 31.53269	2133123.106	6142442.702	54.875
2007.00	33 30 47.52358	117 37 31.54846	2133124.83	6142441.39	

References: RSB 151/1-11, RSB 144/37-48

Description:

FD 2" I.P. WITH 2 1/2" O.C.S. BRASS DISK, STAMPED "RANCHO MISSION VIEJO CORNER 3 1991". STATION IS LOCATED FROM THE INTER OF ORTEGA HWY. AND LA PATA AVE., S'LY ON LA PATA 0.6 MILE TO A.C. RD. WITH GATE ON RIGHT, THROUGH GATE(DA-1) KEEPING RIGHT, 0.2 MILE TO MONUMENT ON THE LEFT.

