

**GPS #:** **4405**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 1023/B-2

City / Location: Unin., Orange County

Scale Factor: 0.99995459

Ellipsoid Red. Factor: 1.00000202

Combination Factor: 0.99995662

Convergence Angle: -00 44 22.39034

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 23 18.26869	117 35 44.95939	2087602.462	6150879.201	-42.319
2007.00	33 23 18.28563	117 35 44.97487	2087604.19	6150877.91	

References: MM 509/10-12, RSB 151/1-11

**Description:**

FD 2 3/4" BRASS DISK, STAMPED "USN CAMP JOSEPH H PENDELTON BOUNDARY LINE WITNESS 1943", FLUSH. STATION IS LOCATED FROM THE INTER OF SAN DIEGO FREEWAY <5> AND CRISTIANITOS RD., SW'LY 100'+/- TO DOUBLE CHAIN LINK GATE ON LEFT, THROUGH GATE AND S'LY DOWN A.C. RD., 0.45 MILE TO ABANDONED BUILDING. MONUMENT IS LOCATED 65'+/- S'LY FROM EDGE OF NW'LY CORNER OF A.C., 11'+/- S'LY ON THE OTHER SIDE OF CHAIN LINK FENCE.

