

GPS #: 4406

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 973/J-7

City / Location: Unin., Orange County

Scale Factor: 0.99995637

Ellipsoid Red. Factor: 0.99998779

Combination Factor: 0.99994417

Convergence Angle: -00 42 29.80620

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 27 18.82826	117 32 20.08125	2111695.517	6168549.772	255.111
2007.00	33 27 18.84514	117 32 20.09663	2111697.24	6168548.49	

References: RSB 8/34-46, RSB 151/1-11

Description:

FD 1 1/2" I.P. WITH 2" BRASS CAP, STAMPED "RANCHO SANTA MARGARITA RE 2838 RE 4231 COUNTY LINE MV CORNER#6", UP 0.5' FROM SURFACE. STATION IS LOCATED FROM THE INTER OF SAN DIEGO FREEWAY <5> AND CRISTIANITOS RD.; E'LY ALONG CRISTIANITOS RD., 2.5 MILES TO CAMP PENDELTON SECURITY GUARD SHACK ON RIGHT, CONTINUE 0.2 MILE TO "Y" INTER, TURN LEFT THEN N'LY ALONG SAN MATEO RD., 1.7 MILES TO "Y" INTER AT GRAVEL RD. BEFORE ENTERING "CAMP TALEGA TACTICAL TRAINING CENTER", TURN RIGHT, ALONG GRAVEL RD. 1.6 MILES E'LY TO MONUMENT LOCATED 50'+/- FROM RIGHT S'LY SIDE OF RD.

