

GPS #: **4407**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 993/F-1

City / Location: Unin., Orange County

Scale Factor: 0.99995622

Ellipsoid Red. Factor: 0.99999316

Combination Factor: 0.99994938

Convergence Angle: -00 43 10.53597

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 27 03.70294	117 33 34.20040	2110245.094	6162251.379	142.910
2007.00	33 27 03.71985	117 33 34.21574	2110246.82	6162250.10	

References: RSB 90/33-42, RSB 151/1-11

Description:

FD 2" BRASS U.S. NAVY DISK IN 6"X 6" CONC. POST, STAMPED "MV-5-1946", FLUSH. STATION IS LOCATED FROM THE INTER OF SAN DIEGO FREEWAY <5> AND CRISTIANITOS RD.; E'LY ALONG CRISTIANITOS RD. 2.5 MILES TO THE CAMP PENDELTON SECURITY GUARD SHACK, CONTINUE 0.2 MILE TO "Y" INTER TURN LEFT ON SAN MATEO RD., PROCEED N'LY 1.7 MILES TO "Y" INTER AT GRAVEL RD. BEFORE ENTERING "CAMP TALEGA TACTICAL TRAINING CENTER", PROCEED E'LY 0.33 MILE ALONG GRAVEL RD. TO MONUMENT LOCATED 125' S'LY AND UPHILL FROM EDGE OF RD.

