

GPS #: **4411R1**

Date Destroyed:

Date Revised: 1/29/2015

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 992/F-2

City / Location: San Clemente

Scale Factor: 0.99995596

Ellipsoid Red. Factor: 1.00000361

Combination Factor: 0.99995956

Convergence Angle: -00 45 56.11605

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 26 36.16700	117 38 35.51936	2107793.032	6136686.116	
2007.00	33 26 36.18402	117 38 35.53494	2107794.77	6136684.82	

References: MM 213/44-46, RSB 151/1-11, CR 2002-1895, CR 2014-2933

Description:

FD GEAR SPIKE AND WASHER STAMPED "LS 6970". MONUMENT WAS RESET PER CORNER RECORD # 2002-1895B IN LIEU OF PUNCHED SPIKE AND 1 1/2" ALUMINUM WASHER (ILLEGIBLE), FLUSH ACCEPTED AS SPIKE AND WASHER STAMPED "RCE 10035", PER MM 213/44-46. STATION IS LOCATED AT THE CENTERLINE POINT OF COMPOUND CURVE ALONG AVENIDA VAQUERO, 30'+/- N'LY FROM ITS INTER WITH VIA CASCADITA.

