

**GPS #:** **4411R2**

Date Destroyed:

Date Revised: 5/29/2015

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 992/F-2

City / Location: San Clemente

Scale Factor: 0.99995596

Ellipsoid Red. Factor: 1.00000361

Combination Factor: 0.99995956

Convergence Angle: -00 45 56.11605

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 26 36.16700	117 38 35.51936	2107793.032	6136686.116	
2007.00	33 26 36.18402	117 38 35.53494	2107794.77	6136684.82	

References: MM 213/44-46, RSB 151/1-11, CR 2002-1895, CR 2014-2933, CR 2015-0460,

**Description:**

FD GEAR SPIKE AND WASHER STAMPED "LS 5411" FLUSH PER CR 2015-0460 IN LIEU OF GEAR SPIKE AND WASHER STAMPED "LS 6970". MONUMENT WAS RESET PER CORNER RECORD # 2002-1895B ORIGINAL MONUMENT BEING PUNCHED SPIKE AND 1 1/2" ALUMINUM WASHER (ILLEGIBLE), FLUSH ACCEPTED AS SPIKE AND WASHER STAMPED "RCE 10035", PER MM 213/44-46. STATION IS LOCATED AT THE CENTERLINE POINT OF COMPOUND CURVE ALONG AVENIDA VAQUERO, 30'+/- N'LY FROM ITS INTER WITH VIA CASCADITA.

