

GPS #: **4425R2**

Date Destroyed:

Date Revised: 9/20/2009

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 952/C-6

City / Location: San Juan Capistrano

Scale Factor: 0.99995911

Ellipsoid Red. Factor: 0.99999297

Combination Factor: 0.99995208

Convergence Angle: -00 46 29.65125

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 30 53.34775	117 39 36.54599	2133854.830	6131867.011	
2007.00	33 30 53.36489	117 39 36.56176	2133856.58	6131865.70	

References: MM 597/1-34, RSB 151/1-11, CR 2001-1059, CR 2009-2372

Description:

FD BRASS NAIL WITH 3/4" BRASS TAG STAMPED "CALTRANS", FLUSH, IN LIEU OF BRASS NAIL AND 1 1/4" OCS BRASS TAG STAMPED "4425R1 5-01" IN POR-ROK, FLUSH, ORIGINAL MONUMENT BEING A GEAR SPIKE WITH BRASS TAG, STAMPED "LS 4599", FLUSH. MONUMENT WAS RESET PER CORNER RECORD # 2001-1059. STATION IS LOCATED AT CENTERLINE INTER OF MARBELLA VISTA AND VIA CONQUISTA.

