

GPS #: **4427R1**

Date Destroyed:

Date Revised: 6/20/2013

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 952/E-7

City / Location: San Juan Capistrano

Scale Factor: 0.99995891

Ellipsoid Red. Factor: 0.99999840

Combination Factor: 0.99995731

Convergence Angle: -00 45 57.07568

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 30 39.98015	117 38 37.26571	2132436.322	6136867.546	
2007.00	33 30 39.99706	117 38 37.28174	2132438.05	6136866.21	

References: RSB 151/1-11, CR 2001-1061, CR 2013-0081

Description:

FD PUNCHED SPIKE WITH CALTRANS WASHER FLUSH, IN LIEU OF LARGE ROUND HEAD SPIKE WITH ALUMINUM WASHER, STAMPED "RCE 10035". MONUMENT WAS RESET PER CORNER RECORD # 2001-1061. STATION IS LOCATED AT THE VISUAL CENTERLINE INTER OF ORTEGA HWY. AND CALLE ENTRADERO.

